

GENERAL NOTES

REVISIONS

Project

Client

Title.



Scale

Drawn

Checked

Clients signature.

Job No.

Clients signature.

GENERAL NOTES

1. All dimensions are in millimeters unless otherwise stated.
2. All dimensions should be checked on site and any discrepancies be reported to the consultant.
3. All works to be carried out in accordance with the local authority.
4. Use figured dimensions only, do not scale from the drawing.
5. Walls less than 200mm thick to be reinforced with hoop iron at every alternative course.
6. DPC to be laid under all walls and to be minimum 150mm above finished ground level.
7. All drainage pipes passing under building and drive way to be encased in 150 mm thick concrete surround.
8. All inspection chambers in driveways to have heavy duty covers.
9. All reinforced concrete works is to be in accordance with structural engineers details.
10. 500 gauge polythene (damp prove membrane) and anti-termite treatment to be provided under ground floor concrete slab.

- [illegible]

[illegible]


Project

Perimeter fence chain link fence gate


Perimeter fence chain link fence gate

International Organisation for Migration.

Title.	Gate details.
---------------	---------------



IOM - OIM
REPUBLIC OF SOUTH SUDAN



Drawn S.K

Checked	Y.S	Job No.	IOM/SS/MARCH/2017
---------	-----	---------	-------------------

Clients signature.

