

NOTES

1. All dimensions are in millimeters unless otherwise stated.
2. All dimensions should be checked on site and any discrepancies be reported to the consultant.
3. All works to be carried out in accordance with the local authority.
4. Use figured dimensions only, do not scale from the drawing.
5. Walls less than 200mm thick to be reinforced with hoop iron at every alternative course.
6. DPC to be laid under all walls and to be minimum 150mm above finished ground level.
7. All drainage pipes passing under building and drive way to be encased in 150 mm thick concrete surround.
8. All inspection chambers in driveways to have heavy duty covers.
9. All reinforced concrete works is to be in accordance with structural engineers details.
10. 500 gauge polythene (damp prove membrane) and anti-termite treatment to be provided under ground floor concrete slab.

REVISIONS

[illegible]


Project

Proposed Pit Toilet.

Client

International Organisation for Migration.

Title.	Elevation,section and floor plan
---------------	-----------------------------------------



Scale

As shown

Date _____

March 2017

Drawn

SK

Checked

Y.S

Drg. No.

01

Job No.

IOM/SS/MARCH/2017

Clients signature.