



International Organization for Migration (IOM)

The UN Migration Agency

Date: 02/05/2023

Addendum No. 7

Construction works for the creation of the Buffer Zone in Pournaras Camp

ITB 2023.CYP.02.BZ

This Addendum No. 7 is issued to amend information provided in the ITB documents and for the “Construction works for the creation of the Buffer Zone in Pournaras Camp” issued to the prospective service providers.

Addendum No. 7

SECTION 3: DATA SHEET

1. Site Inspection

24.	Site inspection	Will not be conducted.
-----	-----------------	------------------------

is replaced with the following:

24.	Site inspection	Interested bidders need to send a request via email to iomgrprocurement@iom.int so as a site inspection to be arranged.
-----	-----------------	---

2. Instruction for bid submission

28.	Instruction for bid submission	Allowable manner of submitting proposals: ■ Courier / hand delivery SUBMISSION BY COURIER / HAND DELIVERY: Bid submission address: 6, Dodekanisou str., 17456. Alimos Athens, Greece
-----	--------------------------------	--

		<p>The bidder shall submit the bid in one sealed envelope containing the technical and price components.</p> <p>For evaluation purposes, a digital copy of the "BoQ_E-M.xls, BoQ-Structural.xlsx and Total cost.xlsx " are required in editable form (xls, xlsx etc.) to be submitted in usb memory stick.</p> <p>The envelope shall indicate the name and address of the bidder.</p> <p>The outer envelope must be clearly marked with the following:</p> <p style="text-align: center;">*ONLY TO BE OPENED BY AUTHORISED PERSONNEL*</p> <p style="text-align: center;">"Construction works for the creation of the Buffer Zone in Pournaras Camp, Cyprus"</p> <p style="text-align: center;">Invitation to Bid Reference: ITB 2023.CYP.02.BZ</p> <p style="text-align: center;">Attention: Procurement dept.</p> <p style="text-align: center;">"Bidders name and details"</p>
--	--	---

is replaced with the following:

28.	Instruction for bid submission	<p>Allowable manner of submitting proposals:</p> <ul style="list-style-type: none"> ■ Courier / hand delivery <p>SUBMISSION BY COURIER / HAND DELIVERY:</p> <p>Bid submission address:</p> <p>6, Dodekanisou str., 17456. Alimos Athens, Greece</p> <p>The bidder shall submit the bid in one sealed envelope containing the technical and price components.</p> <p>For evaluation purposes, a digital copy of the "BoQ_E-M.xls, BoQ-Structural_rev.xlsx and Total cost.xlsx " are required in editable form (xls, xlsx etc.) to be submitted in usb memory stick.</p> <p>The envelope shall indicate the name and address of the bidder.</p> <p>The outer envelope must be clearly marked with the following:</p> <p style="text-align: center;">*ONLY TO BE OPENED BY AUTHORISED PERSONNEL*</p> <p style="text-align: center;">"Construction works for the creation of the Buffer Zone in Pournaras Camp, Cyprus"</p> <p style="text-align: center;">Invitation to Bid Reference: ITB 2023.CYP.02.BZ</p> <p style="text-align: center;">Attention: Procurement dept.</p> <p style="text-align: center;">"Bidders name and details"</p>
-----	--------------------------------	---

3. FORM H: PRICE SCHEDULE

Kindly find the relevant BoQs at links as can be found in SECTION 5: SCHEDULE OF REQUIREMENTS. For evaluation purposes, a digital copy of the “BoQ_E-M.xls, BoQ-Structural.xlsx and Total cost.xlsx ” also required in editable form (xls, xlsx etc.) to be submitted in usb memory stick.

is replaced with the following:

Kindly find the relevant BoQs at links as can be found in SECTION 5: SCHEDULE OF REQUIREMENTS. For evaluation purposes, a digital copy of the” BoQ_E-M.xls, **BoQ-Structural_rev.xlsx** and Total cost.xlsx ” also required in editable form (xls, xlsx etc.) to be submitted in usb memory stick.

4. Changes on BoQ and Technical Documentation

Technical Descriptions and Drawing have been modified. As a result, the list of documents which can be found at the following link [Technical Descriptions and Drawings](#) have been updated accordingly.

For your convenience, you may find in detail the changes which have been made below:

- a. “BoQ-Structural.xlsx” is replaced with “**BoQ-Structural_rev.xlsx**. More specifically, in the tab “Περιβάλλον Χώρος” AT 9 & AT 10 have been modified (see below)

9	Καθαίρεση τμήματος της υφιστάμενης περιφράξης στα σημεία που υποδεικνύονται από την αρχιτεκτονική μελέτη. Περιλαμβάνεται η απεγκατάσταση, η αποθήκευση ενός του έργου και η επανεγκατάσταση της περιφράξης με τη δημιουργία νέων βάσεων θεμελίωσης και σενάζ και προμήθεια όλων των τεμαχίων και μικροϋλικών της περιφράξης που χρειάζονται αντικατάσταση.	Removal of part of the existing fencing at the points indicated by the architectural study. This includes the removal, on-site storage and re-installation of fencing with the creation of new footings and scaffolding and the supply of all fencing parts and hardware that require replacement.	A 031	m	33,00	- €
10	Προμήθεια και τοποθέτηση περιφράξης περιλαμβανομένων των υλικών, συνολικού ύψους 3,0 μέτρων από γαλβανισμένο σιματόπλεγμα και γαλβανισμένους ορθοστάτες διαμέτρου Φ 48 πάχους 2,0 χιλ., πακτωμένους σε σκυρόδεμα σε βάθος τουλάχιστον 50cm με σενάζ 30x30cm εμμηγμένο στο έδαφος κατά 10cm. Περιλαμβάνονται όλα τα παρελκόμενα μικροϋλικά σύμφωνα με τα αντίστοιχα σχέδια και το τεύχος τεχνικής περιγραφής και τεχνικών προδιαγραφών.	Supply and installation of fencing, including the materials, a total height of 3.0 meters of galvanized wire mesh and galvanized posts with a diameter of Φ 48 and a thickness of 2.0 mm, set in concrete to a depth of at least 50cm with a 30x30cm senaz sunk into the ground by 10cm. All accessory micromaterials are included according to the respective drawings and the technical description and technical specifications issue.	A 032	m	550,00	- €

is replaced with the following:

9	Καθαίρεση τμήματος της υφιστάμενης περιφράξης στα σημεία που υποδεικνύονται από την αρχιτεκτονική μελέτη. Περιλαμβάνεται η απεγκατάσταση, η αποθήκευση ενός του έργου και η επανεγκατάσταση της περιφράξης με τη δημιουργία νέων βάσεων θεμελίωσης και σενάζ και προμήθεια όλων των τεμαχίων και μικροϋλικών της περιφράξης που χρειάζονται αντικατάσταση.	Removal of part of the existing fencing at the points indicated by the architectural study. This includes the removal, on-site storage and re-installation of fencing with the creation of new footings and scaffolding and the supply of all fencing parts and hardware that require replacement.	A 031	m	0,00	- €
10	Προμήθεια και τοποθέτηση περιφράξης στην Περιοχή Δραστηριότητας, περιλαμβανομένων των υλικών, συνολικού ύψους 3,0 μέτρων που αποτελείται από τοίχο σκυροδέματος και σχάρα-πάνελ ύψους 2,60μ. Περιλαμβάνονται όλα τα παρελκόμενα μικροϋλικά σύμφωνα με τα αντίστοιχα σχέδια και το τεύχος τεχνικής περιγραφής και τεχνικών προδιαγραφών.	Supply and installation of fencing in Activity Area, including the materials, a total height of 3.0 meters consisting of a concrete wall and grid-panels 2.60m high. All accessory micromaterials are included according to the respective drawings and the technical description and technical specifications issue.	A 032	m	370,00	- €

- b. The documents **1a-i_TEXNIKH PERIGRAΦH_Buffer Zone.docx** and **1a-i_TECHNICAL DESCRIPTION_Buffer Zone.docx** have been replaced with the following documents: **1a-i_TEXNIKH PERIGRAΦH_Buffer Zone_rev.docx** and **1a-i_TECHNICAL DESCRIPTION_Buffer Zone_rev.docx** accordingly. More specifically the changes can be found in article 5. FENCING (5. ΠΕΡΙΦΡΑΞΕΙΣ).
- c. Rub-Hall “Assembly guide 10x32m.pdf” and “Rub-Hall Assembly guide 10x24m.pdf” have been added as per Bid Bulletin no. 2.
- d. “Vendor information Sheet (VIS).pdf” has been added on the link of documents.

Kindly take into consideration any change before the submission of your proposal

All other terms and conditions of the clauses of the ITB with Ref. No. ITB 2023.CYP.02.BZ remain unchanged.